MG-12CP Plant Rigging

Erie Strayer Company
1851 Rudolph Ave.
Erie, PA 16502
(814) 456-7001 phone
(814) 452-3422 fax

The following shows components listed in sequential order of disasssembly

Mixer– 72,000 lbs (MUST CONFIRM WEIGHT ON ERECTION DRAWING)

(1) Crane Pick

Rigging – 20 ft 4-way wire rope bridle with thimbles , 4 shackles

WARNING: ***THIS INFORMATION IS A GUIDELINE ONLY – ALWAYS CONFIRM PROPER RIGGING EQUIPMENT WITH CRANE OPERATOR. SIZE RIGGING EQUIPMENT ACCORDING TO THEIR CERTIFICATIONS – ENSURING THEY EXCEED THE WEIGHT OF MACHINERY BEING LIFTED. ALWAYS REVIEW PLANT ERECTION DRAWINGS FOR PLANT SPECIFIC WEIGHTS; DIFFERENT PLANT CONFIGURATIONS CAN CHANGE THE WEIGHTS LISTED ABOVE***

MG-12CP Plant Rigging

Erie Strayer Company
1851 Rudolph Ave.
Erie, PA 16502
(814) 456-7001 phone
(814) 452-3422 fax

Dust Collector – 12,000 lbs (MUST CONFIRM WEIGHT ON ERECTION DRAWING)

(1) Crane Pick

Rigging – (1) 20 ft 4-way wire rope bridle with thimbles, 2 shackles

Note: *Only two legs from the 4-way will be used

MG-12CP Plant Rigging

Erie Strayer Company
1851 Rudolph Ave.
Erie, PA 16502
(814) 456-7001 phone
(814) 452-3422 fax

<u>Cement Silo</u> – 68,000 lbs (MUST CONFIRM WEIGHT ON ERECTION DRAWING)

(2) Crane Pick, to transition silo from horizontal to vertical position

Rigging – (1) 12 ft spreader bar, (2) 4-way wire rope bridle with thimbles, (2) 10 ft thimble and thimble wire ropes, 8 shackles

Notes: *Only two legs from the 4-way will be used for each crane
*Spreader bar used for rigging to clear fifth wheel and duct work atop of silo
*Spreader bar at tail end of silo not required if correct cable angles are maintained

Erie Strayer Company
1851 Rudolph Ave.
Erie, PA 16502
(814) 456-7001 phone
(814) 452-3422 fax

Aggregate Bin – 21,000 lbs (MUST CONFIRM WEIGHT ON ERECTION DRAWING)

(1) Crane Pick

Rigging – 20 ft 4-way wire rope bridle with thimbles, 4 shackles

Erie Strayer Company
1851 Rudolph Ave.
Erie, PA 16502
(814) 456-7001 phone
(814) 452-3422 fax

Aggregate Travel Frame – 63,000 lbs (MUST CONFIRM WEIGHT ON ERECTION DRAWING)

(2) Crane Pick

Rigging – (2) 20 ft 4-way wire rope bridle with thimbles, 4 shackles

Note: *Only two legs from the 4-way will be used for each crane

Erie Strayer Company
1851 Rudolph Ave.
Erie, PA 16502
(814) 456-7001 phone
(814) 452-3422 fax

Mixer Support Base – 8000 lbs (MUST CONFIRM WEIGHT ON ERECTION DRAWING)

(1) Crane Pick

Rigging – 20 ft 4-way wire rope bridle with thimbles, 4 shackles